

## Fuse table

### Worker ceiling / wall

Maximum loading of automatic of circuit breakers

	Automatic circuit breaker type:	C10	C13	C16	C20	B10	B13	B16	B20	Inrush current
	Installation Ø:	1,5 mm <sup>2</sup>	1,5 mm <sup>2</sup>	2,5 mm	4 mm	1,5 mm <sup>2</sup>	1,5 mm <sup>2</sup>	2,5 mm <sup>2</sup>	4 mm <sup>2</sup>	I <sub>max</sub> time
Driver: Xitanium 75W 0.7-2A 54V TD 230V	Number of drivers:	32	50	56	66	16	25	28	33	3,4 A 358μ*

\* Input voltage 230V, Time measured at 50% I<sub>peak</sub>